

10/03/05

Septic system

3 bedroom home, no dump in
Class III soil

140' of 3" schedule 60 pvc pipe from
shop building and home to 2 each
500 gallon tanks (for 1000 gallon capacity)
① 4"x3" RV dump 90° and 4 each
3" clean out assemblies.

60' of 3" schedule 160 pvc pipe from
septic tanks to drain field manifold
2 each 12.5' x 2' wide ditches
with infiltration panels.

noch clause no object 3849 60

Jim this is a ballpark figure. When
the engineer gets his work done I
can give you a much closer estimate
you have a neighbor that I may use
for a reference on Circle J's work
if you would like

