



PERMIT TO CONSTRUCT
Onsite Wastewater System

Permit ID: OSWW003834 v1.0

County: Calhoun

Name: Roddy Matthews
Type Facility: Residential
Subdivision:
Block: Lot: 40

Site: Lot 40 Ridgelake Cir, ,
Saint Matthews

Program Code: CONVENTIONAL
System Code: 814 INFILTRATOR QUICK
TM #: 1170001051
Water Supply: Municipal

PERMIT TO CONSTRUCT SYSTEM SPECIFICATIONS

Daily Flow (gpd): 480 **Tank Sizes (gal):** Septic Tank: 1000 Pump Chamber: Grease Trap:
LTAR (g/d/ft²): .4 **Trenches:** Length (ft): 300 Width (in): 36 Max. Depth (in): 27 Agg. Depth (in):
Min Pump Capacity: GPM at ft. of Head

SPECIAL INSTRUCTIONS/CONDITIONS

THIS PERMIT IS SITE SPECIFIC. ANY CHANGES TO THE SYSTEM MUST BE APPROVED BY DHEC. ALTERNATIVE TRENCH PRODUCTS APPROVED UNDER STATE RULES AND REGULATIONS MAY BE SUBSTITUTED. ANY UNAPPROVED CHANGES WILL VOID THIS PERMIT.

Installers must contact the local Environmental Affairs office by 10:00 AM the day prior to installation in order to schedule a time for the final inspection. If a Department representative does not arrive within 30 minutes of the scheduled time, the installer may conduct the final inspection. When a contractor self-inspection occurs, the installer must complete DHEC form 3978, Approval to Operate Contractor Self-Inspection. The installer must submit the DHEC form 3978 within 2 business days of the completion of installation.

Self-installations require a pre-construction conference with a Department representative.

- *All applicable setbacks set forth in Regulation 61-56 apply.*

PERMIT TO CONSTRUCT SYSTEM DIAGRAM

See System Diagram on page 2 of this document.

Adrian Mack

Issued/Revised By:

Date: August 07, 2023



PERMIT TO CONSTRUCT
Onsite Wastewater System

Applicant: Roddy Matthews
Permit ID: OSWW003834 v1.0
County: Calhoun

PERMIT TO CONSTRUCT SYSTEM DIAGRAM

- INSTALL FOUR 75' LINES OF STANDARD QUICK 4 INFILTRATOR
- INSTALL LINES ON CONTOUR

