



PERMIT TO CONSTRUCT
Onsite Wastewater System

Permit ID: OSWW009673 v1.0

County: Kershaw

Name: Jason Hackworth
Type Facility: Residential
Subdivision: Not Named - Pre
existing family division
Block: Lot: 3

Site: 2215 Porter Rd., , Cassatt

Program Code: CONVENTIONAL
System Code: 804 EZFLOW 1203H
TM #: 169-00-00-082
Water Supply: Municipal

PERMIT TO CONSTRUCT SYSTEM SPECIFICATIONS

Daily Flow (gpd): 480 **Tank Sizes (gal):** Septic Tank: 1000 Pump Chamber: Grease Trap:
LTAR (g/d/ft²): .8 **Trenches:** Length (ft): 150 Width (in): 36 Max. Depth (in): 26 Agg. Depth (in): 12
Min Pump Capacity: GPM at ft. of Head

SPECIAL INSTRUCTIONS/CONDITIONS

THIS PERMIT IS SITE SPECIFIC. ANY CHANGES TO THE SYSTEM MUST BE APPROVED BY DHEC. ALTERNATIVE TRENCH PRODUCTS APPROVED UNDER STATE RULES AND REGULATIONS MAY BE SUBSTITUTED. ANY UNAPPROVED CHANGES WILL VOID THIS PERMIT.

Installers must contact the local Environmental Affairs office by 10:00 AM the day prior to installation in order to schedule a time for the final inspection. If a Department representative does not arrive within 30 minutes of the scheduled time, the installer may conduct the final inspection. When a contractor self-inspection occurs, the installer must complete DHEC form 3978, Approval to Operate Contractor Self-Inspection. The installer must submit the DHEC form 3978 within 2 business days of the completion of installation.

Self-installations require a pre-construction conference with a Department representative.

- *Maximum Trench Depth not to exceed 26 inches. Place lines on contour and use serial distribution if needed.*
- *Permit issued for 1203 H EZ FLOW. No further reduction allowed.*
- *This system is designed for specific quantities of domestic wastewater ONLY.*
- *All applicable setbacks set forth in Regulation 61-56 apply.*
- *Do not install under wet soil conditions. Minimum 9" cover over system after installation.*
- *No parking, driving, building or paving over the area of septic system before or after installation.*
- *Do not cut, fill, bulldoze, scrape or change the grade of the natural soils in the septic system area.*
- *Pre-construction conference required for property owners who wish to install their own system.*
- *75' setback from all private wells. 100' setback from public wells.*

PERMIT TO CONSTRUCT SYSTEM DIAGRAM

See System Diagram on page 2 of this document.

Issued/Revised By:

Cindy Taylor

Date: August 30, 2023



PERMIT TO CONSTRUCT

Onsite Wastewater System

Applicant: Jason Hackworth

Permit ID: OSWW009673 v1.0

County: Kershaw

PERMIT TO CONSTRUCT SYSTEM DIAGRAM

